



Scope of Work (Final)

January 01, 2026

Submitted to:

MIOYM-PROJECT MANAGEMENT

Submitted by:

Mioym Equities Inc
2900 Westchester Avenue Suite 302
Purchase , NY 10577
Business: 914-566-9050 Ect. 103
Mobile: 718-536-7050
Fax: 888-801-9401
Business: const@mioym.com

CONTRACTOR INFORMATION

ABSOLUTE RENOVATIONS LLC

2611 S PENNSYLVANIA STREET

INDIANAPOLIS, IN 46225

Mr. Alex Artega

CONTRACTOR REQUIREMENTS AND WORK EXECUTION GUIDLINES

GENERAL CONDITIONS

- General Contractor to provide all necessary labor and materials
- Perform all work of every nature on the proposed remodeling following the agreed-upon scope of work, executed contract, all detailed specifications, and any accompanying drawings.
- General Contractor to obtain all building required permits and schedule all inspections per building and zoning requirements.
- All subcontractors will obtain and pay for their permits as well.
- The owner will, if necessary, have the lot surveyed and apply for all zoning, historic preservation, or other related permits as necessary. Work for any of these is not included under this contract.
- All work is to be executed in a workman-like manner and in full compliance with the contract, plans, specifications, and applicable construction standards, including but not limited to local building codes, industry best practices, and relevant safety regulations.

DOCUMENTATION FOR QUANTITIES AND VALUES

- Weekly visual **walkthroughs** are mandatory to provide consistency in the project process and funding. Scheduled Monday-Thursday.
- The contractor **must submit photos/videos** to verify and confirm the quantities and value of work completed, as

outlined in the Scope of Work (SOW) for inspections and funding of draws.

- All DRAWS must be requested with a **6-7 day** schedule and reviewed promptly for inspections.
- DRAWS will only be funded if the work is complete and meets the required standards.
- The general contractor is responsible for all permits and scheduling of inspections.

SCOPE OF WORK

- The contractor is required to **match and fulfill each item** explicitly indicated in the Scope of Work (SOW).
- Any necessary additional work that is not specified in the SOW will be discussed with MIOYM PROJECT MANAGEMENT and must be approved first and amended to the original SOW.

LICENSING, INSURANCE, AND BONDING REQUIREMENTS

- Possess **valid licenses** appropriate for the type of work being performed.
- Be fully **insured**, meeting or exceeding the minimum insurance requirements as defined in the contract or by applicable laws.
- Be **bonded** to ensure the performance of the agreed-upon work.

Payments:

All payments are made via wire with a \$25.00 service fee unless otherwise noted or requested via invoice and check.

Project Specifications

1045 ORANGE STREET, CENTER TOWNSHIP, IN 46203

RENOVATION OF A 1910 2-STORY SFR, 3 BEDROOM, 1 BATHROOM, FULL KITCHEN 1232 +/- SQ FT

C00/PRE-CONSTRUCTION

PERMITS, ALL PROFESSIONAL FEES, DEMOLITION AND REMOVAL OF ALL FIRE DAMAGED MATERIAL AND CONSTRUCTION DEBRIS, HAUL AND CLEAR LANDSCAPING AND GRADE AWAY FROM FOUNDATION

PROJECT PREPARATION

- | | |
|--|------------|
| ■ Building permit fee/inspection fees/professional fees (TBD) | \$1,300.00 |
| ■ Load, haul & dump clean construction debris, 4.5 cubic yards | \$2,100.00 |

GENERAL DEMOLITION

- | | |
|-------------------------------|------------|
| ■ General interior demolition | \$2,000.00 |
|-------------------------------|------------|

FENCING AND LANDSCAPING

- | | |
|--------------------------------------|------------|
| ■ Miscellaneous expenses - landscape | \$1,000.00 |
|--------------------------------------|------------|

Sub-Total is \$6,400.00

C01/EXTERIOR

REPAIR EXTERIOR SIDING, PREP AND PAINT, ALL FACIA, SOFFITS, AND TRIMS, CAULK SEAL ALL FOUNDATION CRACKS AND VOIDS, AND PAINT, REBUILD FRONT PORCH WITH RAILING AND SKIRT, REPAIR ALL WALKWAY, CONCRETE STEPS, AND REPLACE 2 EXTERIOR DOORS, REPAIR EXTERIOR REAR CHAINLINK FENCE AND EXTEND AROUND PROPERTY,

MASONRY

- | | |
|-----------------------------|------------|
| ■ All exterior masonry work | \$2,100.00 |
|-----------------------------|------------|

EXTERIOR DOORS

■ Replace front exterior door with JELD-WEN Smooth Pro 36 in. x 80 in. 2 Panel Left Hand 6 Lite Clear Black Fiberglass Prehung Front Door w/ White Interior Finish	\$1,480.00
--	------------

DECKS AND PORCHES

■ Rebuild front wooden porch/deck with railing and skirts	\$2,050.00
---	------------

EXTERIOR TRIM

■ Repair-replace all fascia,soffit,trims	\$900.00
--	----------

EXTERIOR PAINTING

■ Paint all exterior vinyl and trims	\$3,000.00
--------------------------------------	------------

FENCING AND LANDSCAPING

■ Repair and extend 4 foot calvanized chain link fence with gate	\$2,500.00
--	------------

LANDSCAPING & FENCING

■ Remove or trim all overgrown trees next to property foundation	\$800.00
--	----------

Sub-Total is \$12,830.00

C02/ROOF AND GUTTERS

REPAIR -REPLACE ALL DAMAGED SHINGLES, GUTTERS, AND DOWNSPUOTS, REPLACE ALL DRIP EDGE AND FLASHINGS, PLUMBING VENTS, CHIMNEY FLASHING AND RAIN CAP

ROOFING AND GUTTERS

■ Roof anf gutter budget	\$3,980.00
--------------------------	------------

Sub-Total is \$3,980.00

C03/WINDOWS

REMOVE AND INSTALL ALL DAMAGED WINDOWS, CAULK, SEAL AND WRAP, INCLUDING BASEMENT WINDOWS

VINYL WINDOWS

■ Provide and Install American Craftsman 70 Series White Double Hung Low-E Argon Glass Vinyl Fin with J Window, Screen Incl OR SIMILAR	\$8,037.73
--	------------

Sub-Total is \$8,037.73

C04/ELECTRICAL

RE-WIRE OF ELECTRICAL COMPONENTS AND UPGRADE OF PANEL

ELECTRICAL

■ Electrical budget	\$7,250.00
---------------------	------------

Sub-Total is \$7,250.00

C05/PLUMBING

INSTALLATION OF ALL NEW PEX PLUMBING LINES FOR 1 BATHROOM 1 KITCHEN, HOT AND COLD INCLUDING WASTE LINES AND DRAINAGE

GENERAL PLUMBING

■ Installation of all new plumbing	\$6,700.00
------------------------------------	------------

Sub-Total is \$6,700.00

C06/HVAC

INSTALLATION OF NEW ELECTRICAL HEAT PUMP UNIT (2-2.5 TONS) WITH ALL COMPONENTS INCLUDING INDOOR AIR HANDLERS AND DUCT WORK

HEATING, VENTILATION, AIR CONDITIONING

■ Installation of electrical sourced heat pump	\$8,500.00
--	------------

Sub-Total is \$8,500.00

C07/KITCHEN

RENOVATE FULL KITCHEN WITH INSTALLATION OF NEW APPLIANCES, FLOORING AND CABINETS

GENERAL DEMOLITION

■ Remove 100 sq. feet of gypsum drywall from ceiling.	\$62.55
■ Remove 75 sq. feet of resilient sheet flooring, adhesive set.	\$59.42
■ Remove 230 sq. feet of gypsum drywall from wall.	\$105.50
■ Remove 27 lin. feet of kitchen cabinet(s), base or wall.	\$270.22

KITCHEN AND LAUNDRY PLUMBING

■ Labor to install 1 new sink and faucet in prepared location.	\$167.23
■ Provide 1 kitchen sink, enameled steel, 38" x 22", average grade. Fixture cost only, no labor included.	\$250.00
■ Provide KOHLER Elmbrook Single-Handle Pull-Down Sprayer Kitchen Faucet in Vibrant Stainless OR SIMILAR. Fixture cost only, no installation included.	\$189.00
■ Install In SinkErator Badger 500, 1/2 HP Continuous Feed Kitchen Garbage Disposal, Badger Series OR SIMILAR in prepared location. No removal or rough-in included.	\$261.40
■ Remove 1 sink and faucet.	\$60.30

ELECTRICAL

■ Provide and install 4 GFIC outlets in existing box(es).	\$249.42
■ Install (6) HALO HLBSL 4 in. Adjustable CCT Canless IC Rated Dimmable Indoor, Outdoor Integrated LED Recessed Light Kit OR SIMILAR in existing box. Within 10' of power source. No patching included.	\$83.53
■ Rough-in 1 refrigerator wall outlet, with open walls and ceiling below. No appliance included.	\$117.26
■ Rough-in 1 hood & fan outlet, with open walls and ceiling below. No appliance included.	\$117.26

APPLIANCES

■ Install Broan-NuTone Glacier BCSQ1 30 in. 375 Max Blower CFM Convertible Under-Cabinet Range Hood with Light in Stainless Steel OR SIMILAR. No removal or rough-in included.	\$276.76
■ Install Frigidaire 24 in Front Control Built-In Tall Tub Dishwasher in Stainless Steel with 4-cycles and Dish Sense Sensor Technology OR SIMILAR in prepared location. No removal or rough-in included.	\$484.64

WALL COVERINGS

■ Provide and install 230 sq. feet of drywall, taped and finished, 1/2".	\$508.44
--	----------

CEILING COVERINGS

■ Provide and install 100 sq. feet of drywall ceiling, taped and finished, 1/2".	\$260.21
--	----------

INTERIOR TRIM, STAIRS AND ACCESSORIES

■ Install Woodgrain Millwork 126 1/2 in. x 3/4 in. x 96 in. Primed Finger Jointed Shoe Moulding (1-Piece – 8 Total Linear Feet) OR SIMILAR	\$56.30
■ Install WM 623 9/16 in. x 3 1/4 in. x 144 in. Pine Primed Finger-Jointed Baseboard Molding Pro-Pack 120 LF (10-Pieces) OR SIMILAR	\$85.36

CABINETS AND COUNTERTOPS

■ Install Hampton Bay Hampton 36 in. W x 24 in. D x 34.5 in. H Assembled Base Kitchen Cabinet in Satin White with Drawer Glides. OR SIMILAR	\$1,463.55
---	------------

■ Install Hampton Bay Hampton 30 in. W x 12 in. D x 30 in. H Assembled Wall Kitchen Cabinet in Satin White OR SIMILAR	\$1,549.01
■ Install laminate countertop, Hampton Bay 8 ft. Straight Laminate Countertop in Textured Calcutta Marble with Eased Edge and Integrated Backsplash OR SIMILAR	\$480.10

FLOOR COVERING

■ Provide and install 75 sq. feet of cement board/wonderboard/durock, 1/2".	\$371.36
■ Provide TrafficMaster Skyland 6 MIL x 6 in. W x 36 in. L Waterproof Click Lock Rigid Core Luxury Vinyl Plank Flooring OR SIMILAR . Material costs only, labor not included.	\$378.26

INTERIOR PAINTING AND WALLPAPER

■ Paint wall, BEHR PRO 5 gal. #52 White Eggshell Interior Paint OR SIMILAR over smooth finish, latex, roll, 2 coats	\$272.27
■ Paint ceiling, BEHR PREMIUM PLUS 5 gal. #PR-W15 Ultra-Pure White Ceiling Flat Interior Paint OR SIMILAR over smooth finish, latex, roll, 2 coats	\$124.11
■ Paint baseboard, BEHR PRO 1 gal. i300 White Semi-Gloss Interior Paint OR SIMILAR , up to 4" wide, latex, 2 coats	\$31.44

Sub-Total is \$8,334.90

C08/BATHROOM

RENOVATE BATHROOM, NEW CABINETS, HARDWARE, SHOWER/TUB, AND TILE FLOORING

BATHROOM PLUMBING

■ Remove 1 toilet and replace flange.	\$136.69
■ Remove 1 sink, pedestal or wall mount.	\$59.50
■ Remove 1 cast iron tub.	\$237.98
■ Labor to install 1 new vanity cabinet and top, with single sink and faucet, in prepared location.	\$243.61
■ Labor to install 1 new fiberglass or acrylic tub and faucet in prepared location.	\$324.82
■ Provide and install 1 toilet, 2 piece, elongated, average grade, in prepared location.	\$511.40
■ Provide 1 bathtub, acrylic, average grade. Fixture cost only, no labor included.	\$680.00
■ Provide 1 sink faucet, single lever control, average grade. Fixture cost only, no labor included.	\$187.00
■ Provide and install 1 designer shower faucet set and valve.	\$595.07
■ Provide 1 bathroom vanity sink, self rim, 20" x 17", average grade. Fixture cost only, no labor included.	\$200.00
■ Provide 1 vanity cabinet, 35" x 19", 2 door, average grade. vanity cabinet cost only, no labor included.	\$350.00
■ Provide 1 laminate vanity top, 35" x 19". Vanity top cost only, no labor included.	\$101.00

ELECTRICAL

■ Provide and install 1 GFIC outlet in existing box(es).	\$62.36
■ Remove and provide bathroom light/fan/heater Broan-NuToneQT Series 130 CFM Ceiling Bathroom Exhaust Fan with LED Light and Night Light, ENERGY STAR OR SIMILAR	\$357.95

WALL COVERINGS

■ Provide and install 120 sq. feet of drywall, taped and finished, 1/2".	\$265.27
■ Provide and install drywall, 1 area, moisture resistant, finished, 1/2", up to 100 SF of total area.	\$492.42
■ Labor to install 75 sq. feet of 6 x 6 ceramic tile wall, in adhesive, grout and seal.	\$1,106.40
■ Provide 75 sq. feet of ceramic tile wall covering, 4-1/4" to 12".	\$75.00

CEILING COVERINGS

■ Provide and install 50 sq. feet of drywall ceiling, taped and finished, 5/8".	\$137.37
---	----------

INTERIOR DOORS

■ Remove 1 single interior door, including jamb and casing.	\$48.92
---	---------

■ Provide and install 1 interior pre-hung fir/pine 6 panel door unit, 2-4 x 6-8.	\$354.37
--	----------

INTERIOR TRIM, STAIRS AND ACCESSORIES

■ Glacier Bay Constructor 3-piece Bath Hardware Set includes 24 in. Towel Bar, Towel Ring and TP Holder in Chrome OR SIMILAR	\$145.00
--	----------

FLOOR COVERING

■ Labor to install 41 sq. feet of 12 x 12 ceramic tile floor. No flooring materials included.	\$464.37
---	----------

■ Provide and install 41 sq. feet of cement board/wonderboard/durock, 1/2".	\$203.01
---	----------

■ Provide ceramic tile flooring, 41 sq. feet, 4-1/4" to 12". Material costs only, labor not included.	\$205.00
---	----------

INTERIOR PAINTING AND WALLPAPER

■ Paint flush bi-fold door(s), 2 sides, brush, 2 coats, 4' to 6', water based paint. Includes jamb & casing.	\$127.64
--	----------

■ Paint wall, BEHR PRO 5 gal. #52 White Eggshell Interior Paint OR SIMILAR over smooth finish, latex, roll, 2 coats	\$106.54
---	----------

■ Paint ceiling, BEHR PREMIUM PLUS 5 gal. #PR-W15 Ultra-Pure White Ceiling Flat Interior Paint OR SIMILAR over smooth finish, latex, roll, 2 coats	\$62.05
--	---------

Sub-Total is \$7,840.74

C09/BEDROOMS

RENOVATION OF 3 BEDROOMS, WALLS, CEILINGS, FLOORING, ELECTRIC, AND ALL TRIMS AND FRAMES

GENERAL DEMOLITION

■ Remove 500 sq. feet of gypsum drywall from ceiling.	\$312.75
---	----------

■ Remove 1 single interior wood door.	\$30.86
---------------------------------------	---------

■ Remove 1,200 sq. feet of gypsum drywall from wall.	\$550.44
--	----------

ELECTRICAL

■ Provide and install 6 box and duplex outlet sets, open walls, within 10' of power.	\$360.93
--	----------

■ Provide and install 3 box and switch sets, open walls, within 10' of power.	\$180.47
---	----------

■ Provide and install 3 3 way switch sets, open walls, within 10' of power.	\$599.23
---	----------

■ Provide and install 3 ceiling box(es), open walls, within 10' of power.	\$180.47
---	----------

■ Provide and install 3 ceiling box and wall switch sets, finished walls, within 10' of power.	\$1,136.06
--	------------

■ Install Home Decorators Collection Merwry 52 in. Integrated LED Indoor Matte Black Ceiling Fan with Light Kit and Remote Control Within 10' of power source. No patching.	\$710.51
---	----------

WALL COVERINGS

■ Provide and install 1,200 sq. feet of drywall, taped and finished, 1/2".	\$2,652.72
--	------------

CEILING COVERINGS

■ Provide and install 500 sq. feet of drywall ceiling, taped and finished, 1/2".	\$1,301.07
--	------------

INTERIOR DOORS

■ Install Kwikset Casey Matte Black Bed/Bath Privacy Door Handle Featuring Microban with Lock	\$141.53
---	----------

■ Provide and install 1 interior pre-hung fir/pine 6 panel door unit, 2-6 x 6-8.	\$354.37
--	----------

INTERIOR TRIM, STAIRS AND ACCESSORIES

- Install Woodgrain Millwork 126 1/2 in. x 3/4 in. x 96 in. Primed Finger Jointed Shoe Moulding (1-Piece – 8 Total Linear Feet) OR SIMILAR \$324.83
- Provide and install 150 lin. feet of pine base, 9/16 x 4-1/4, decorative. \$836.74

FLOOR COVERING

- Provide and install TrafficMaster Soared - Sky High - Gray 12 ft. 30 oz. SD Polyester Texture Full Roll Carpet and underlayment if necessary OR SIMILAR \$3,606.25

INTERIOR PAINTING AND WALLPAPER

- Paint int. panel door, 2 sides, brush, 1 coat, water based paint. Includes jamb & casing. \$51.59
- Paint windows(s) and trim, 1 side, 12 to 22 SF, up to 4 lites, 2 coats (interior). \$57.45
- Paint wall, BEHR PRO 5 gal. #52 White Eggshell Interior Paint OR SIMILAR over smooth finish, latex, roll, 2 coats \$1,420.56
- Paint ceiling, BEHR PREMIUM PLUS 5 gal. #PR-W15 Ultra-Pure White Ceiling Flat Interior Paint OR SIMILAR over smooth finish, latex, roll, 2 coats \$620.53
- Paint baseboard, BEHR PRO 1 gal. i300 White Semi-Gloss Interior Paint OR SIMILAR , up to 4" wide, latex, 2 coats \$181.39

Sub-Total is \$15,610.75

C10/INTERIOR

REMODEL ALL COMMON AREA, DINING ROOM, HALL AND ENTRANCE

GENERAL DEMOLITION

- Remove 300 sq. feet of gypsum drywall from ceiling. \$187.65
- Remove 1 single interior wood door. \$30.86
- Remove 558 sq. feet of gypsum drywall from wall. \$255.95

ELECTRICAL

- Provide and install 5 box and duplex outlet sets, open walls, within 10' of power. \$300.78
- Provide and install 5 box and switch sets, open walls, within 10' of power. \$300.78
- Provide and install 5 3 way switch sets, open walls, within 10' of power. \$998.71
- Provide and install 5 ceiling box(es), open walls, within 10' of power. \$300.78
- Provide and install 5 ceiling box and wall switch sets, finished walls, within 10' of power. \$1,893.44
- Provide and install 5 ceiling lights in existing box, average grade. \$819.19

WALL COVERINGS

- Provide and install 558 sq. feet of drywall, taped and finished, 1/2". \$1,233.52

CEILING COVERINGS

- Provide and install 300 sq. feet of drywall ceiling, taped and finished, 1/2". \$780.64

INTERIOR TRIM, STAIRS AND ACCESSORIES

- Install Woodgrain Millwork 126 1/2 in. x 3/4 in. x 96 in. Primed Finger Jointed Shoe Moulding (1-Piece – 8 Total Linear Feet) OR SIMILAR \$149.42
- Provide and install 69 lin. feet of pine base, 9/16 x 4-1/4, decorative. \$384.90

FLOOR COVERING

- Labor to install 300 sq. feet of laminate or engineered flooring. No flooring materials included. \$704.48

- Provide laminate flooring, 300 sq. feet, prefinished, alum. oxide, 7-5/8x47-1/4x5/16. Material costs only, labor not included. \$1,122.00

INTERIOR PAINTING AND WALLPAPER

- Paint windows(s) and trim, 6 sides, 12 to 22 SF, up to 4 lites, 2 coats (interior). \$344.67
- Paint wall, BEHR PRO 5 gal. #52 White Eggshell Interior Paint OR SIMILAR over smooth finish, latex, roll, 2 coats \$660.56
- Paint ceiling, BEHR PREMIUM PLUS 5 gal. #PR-W15 Ultra-Pure White Ceiling Flat Interior Paint OR SIMILAR over smooth finish, latex, roll, 2 coats \$372.32
- Paint baseboard, BEHR PRO 1 gal. i300 White Semi-Gloss Interior Paint OR SIMILAR , up to 4" wide, latex, 2 coats \$83.44

INTERIOR PAINTING

- Paint 2 interior panel doors with 2 coats including jamb & casing (cost per side). \$6.00

Sub-Total is \$10,930.09

C11/STRUCTURAL/FOUNDATION

REPAIR ALL DAMAGED FOUNDATION, STRUCTURAL AND SUBFLOORING

FLOOR FRAMING

- All damaged subflooring \$2,100.00

WALL FRAMING

- All damaged wall framing \$2,700.00

CONCRETE & MASONRY

- All damaged foundation \$15,000.00
- Tuckpoint chimney \$350.00

Sub-Total is \$20,150.00

C12/BASEMENT

CAULK AND SEAL ALL LARGE VOIDS IN FLOORING AND WALLS, DRYLOCK ALL WALLS, CEILING, AND FLOORING, INSTALL LIGHTING, DRYER AND WASHER CONNECTIONS, INSTALL LUANDRY TUB

MASONRY

- Caulk and seal all cracks and voids in walls, flooring, and ceiling with elastomeric sealant. \$1,850.00

GENERAL PLUMBING

- Laundry tub and washer connections \$800.00

ELECTRICAL

- Install dryer connection \$350.00

INTERIOR PAINTING AND WALLPAPER

- Waterproof basement walls/ceiling/floors with Drylock paint \$1,500.00

Sub-Total is \$4,500.00

C13/INSULATION

INSTALL INSULATION ON ALL EXTERIOR FACING WALLS, ATTIC CRAWL SPACE AND BASEMENT FLOOR JOIST

INSULATION

- Install insulation for energy efficiency \$2,500.00

Sub-Total is \$2,500.00

C14/POST CONSTRUCTION

FINAL PROJECT FINISHES AND DEEP CLEANING INCLUDING, INSTALLATION OF APPLIANCES AND FINAL LANDSCAPING

APPLIANCES

- Appliance Package (refrigerator, stove, microwave, dishwasher) TO BE PURCHASED BY OWNER \$2,500.00

PROJECT FINALIZATION

- Post construction cleaning \$400.00
- Trim, grade and cut grass if necessary \$600.00
- Remove and replace mailbox and post in concrete. \$137.00

Sub-Total is \$3,637.00

Project Cost is \$127,201.00

THE FOLLOWING PROPOSAL IS SUBMITTED BY:

Signature  Date: 01/06/2026

Construction Project Manager

ACCEPTANCE OF PROPOSAL

The prices, specifications, and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined in this contract.

Signature Marc A Cox Date: 01/06/2026
President, MIOYM

Signature Alex Artega Date: 01/06/2026

General Contractor



Completed Document Audit Report

Completed with SignWell.com

Title: 1045 Orange Street \$127,201.00 (CONTRACTOR)

Document ID: ee676524-742a-42f3-b366-b4d62a745810

Time Zone: (GMT+00:00) Coordinated Universal Time

Files

1045 Orange Street \$127,201.00 (CONTRACTOR).pdf - 9 pages

Jan 02, 2026 04:51:02 UTC

Activity

	Mioym Construction	created the document (const@mioym.com)	Jan 02, 2026 04:51:54 UTC
IP: 2603:7000:d440:fd96:254d:5cdd:7fd:dbf6			
	Mioym Construction	sent the document to const@mioym.com, mcox@mioym.com, and aarteaga@absoluterenovations.co	Jan 02, 2026 04:54:48 UTC
IP: 2603:7000:d440:fd96:254d:5cdd:7fd:dbf6			
	Marc A Cox	first viewed document (mcox@mioym.com)	Jan 02, 2026 19:21:25 UTC
IP: 2600:480a:3473:a000:4c7f:3226:c568:33db			
	Marc A Cox	signed the document (mcox@mioym.com)	Jan 02, 2026 19:21:38 UTC
IP: 2600:480a:3473:a000:4c7f:3226:c568:33db			
	Alex Artega	first viewed document (aarteaga@absoluterenovations.co)	Jan 06, 2026 00:33:06 UTC
IP: 73.103.96.91			
	Alex Artega	signed the document (aarteaga@absoluterenovations.co)	Jan 06, 2026 15:12:38 UTC
IP: 73.103.96.91			
	Mioym Construction	re-sent the document to const@mioym.com, mcox@mioym.com, and aarteaga@absoluterenovations.co	Jan 06, 2026 15:43:47 UTC
IP: 108.58.208.94			

 Marcos Loffredo	first viewed document (const@mioym.com)	Jan 06, 2026 15:44:08 UTC
IP: 108.58.208.94		
 Marcos Loffredo	signed the document (const@mioym.com)	Jan 06, 2026 15:44:45 UTC
IP: 108.58.208.94		